

FILED

CITY OF SACRAMENTO  
Department of Transportation  
Engineering Services Division

Bid Proposal (Revised 6/25/07)

JUN 27 2007

Page 1 of 5

By The  
Office of The City Clerk

TO THE HONORABLE CITY COUNCIL  
SACRAMENTO, CALIFORNIA:

In compliance with the Contract Documents, the undersigned hereby proposes to furnish all required labor, materials, supervision, transportation, equipment, services, taxes and incidentals required for:

**DEL PASO ROAD WIDENING PROJECT (PN: TW86)**

in the City and County of Sacramento, California.

The Work is to be done in strict conformity with the Contract Documents now on file in the office of the City Clerk, for the following sum:

Item No.	Item	Estimated Quantity	Unit	Unit Price	Total
1	PHOTOGRAPHS	1	LS	\$ 300. <sup>00</sup>	\$ 300. <sup>00</sup>
2	CLEARING AND GRUBBING	1	LS	\$ 84,500. <sup>00</sup>	\$ 84,500. <sup>00</sup>
3	POTHOLING	30	EA	\$ 350. <sup>00</sup>	\$ 10,500. <sup>00</sup>
4	ROADWAY EXCAVATION AND GRADING (F)	17,487	CY	\$ 22. <sup>00</sup>	\$ 384,714. <sup>00</sup>
5	UNSUITABLE MATERIAL	3,000	TN	\$ 15. <sup>00</sup> De	\$ 45,000. <sup>00</sup> De
6	GEOGRID MATERIAL	5,000	SY	\$ 5. <sup>00</sup>	\$ 25,000. <sup>00</sup>
7	AGGREGATE BASE CLASS 2	12,611	TN	\$ 32. <sup>00</sup>	\$ 403,552. <sup>00</sup>
8	ASPHALT CONCRETE PAVEMENT	3,874	TN	\$ 83. <sup>00</sup>	\$ 321,542. <sup>00</sup>
9	3 1/2" SIDEWALK TO PLACE	33,240	SF	\$ 5. <sup>00</sup>	\$ 166,200. <sup>00</sup>
10	CURB AND GUTTER NO. 4 TO PLACE	4,140	LF	\$ 14. <sup>00</sup>	\$ 57,960. <sup>00</sup>
11	REINFORCED CURB AND GUTTER NO. 4	350	LF	\$ 32. <sup>00</sup>	\$ 11,200. <sup>00</sup>
12	MODIFIED CURB NO. 14A TO PLACE	4,685	LF	\$ 13. <sup>00</sup>	\$ 60,905. <sup>00</sup>
13	MODIFIED CURB NO 14B TO PLACE	2,625	LF	\$ 17. <sup>00</sup>	\$ 44,625. <sup>00</sup>
14	TEMPORARY DIVIDER CURB TO PLACE	150	LF	\$ 20. <sup>00</sup>	\$ 3,000. <sup>00</sup>
15	6" CONCRETE COMMERCIAL DRIVEWAY	1,632	SF	\$ 9. <sup>00</sup>	\$ 14,688. <sup>00</sup>
16	ADJUST PULL BOX TO GRADE	27	EA	\$ 400. <sup>00</sup>	\$ 10,800. <sup>00</sup>
17	TRUNCATED DOMES TO PLACE	11	EA	\$ 800. <sup>00</sup>	\$ 8,800. <sup>00</sup>
18	12" DIAMETER DRAIN LEAD TO PLACE	136	LF	\$ 50. <sup>00</sup>	\$ 6,800. <sup>00</sup>
19	15" DIAMETER DRAIN LEAD TO PLACE	535	LF	\$ 130. <sup>00</sup>	\$ 69,550. <sup>00</sup>
20	18" DIAMETER DRAIN LEAD TO PLACE	110	LF	\$ 60. <sup>00</sup>	\$ 6,600. <sup>00</sup>
21	STORM DRAIN MH NO. 3 TO PLACE	1	EA	\$ 4,500. <sup>00</sup>	\$ 4,500. <sup>00</sup>